

**BRUHATH BANGALORE MAHA
DTS**

LIKE

Issued to Sri

TEND NO:
ITEM NO:
Original/Duplicate

NAME OF WORK: Improvements of ground surrounding segregant point in ward no 17 (North side)

Sl. No	Qty	Description of work	Unit	Tender Rate	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	329.36	Earthwork in surface excavation in Hard soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications	cum	157.68	Rupees One Hundred Fifty Seven and Sixty Eight Paise Only
2	109.79	Providing and Filling in foundation with granite / trap broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. complete as per specifications	cum	1135.08	Rupees One Thousand One Hundred Thirty Five and Eight Paise Only
3	109.790	Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications.	cum	1059.48	Rupees One Thousand Fifty Nine and Forty Eight Paise Only
4	91.49	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	cum	3884.76	Rupees Three Thousand Eight Hundred Eighty Four and Seventy Six Paise Only
5	84.17	Providing and laying cement concrete using 20 mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) for R.C.C works laid in 15 cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 for raft foundation, column footing, main and secondary beams	cum	5639.76	Rupees Five Thousand Six Hundred Thirty Nine and Seventy Six Paise Only

DTS Approved

[Signature]

21/12

ಮುಖ್ಯ ಅಧೀಕ್ಷಕರು
ಪ್ರಾ.ಪಂ.ಬೆಂಗಳೂರು
ಪ್ರಾ.ಪಂ.ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

[Signature]
Signature of the contractor

[Signature]
Executive Engineer
RRNagara Division
BBMP

6	84.17	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	qtl	7323.48	Rupees Seven Thousand Three Hundred Twenty Three and Forty Eight Paise Only
7	365.96	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift.	sqm	86.40	Rupees Eighty Six and Forty Paise Only
8	58.75	Providing groove cutting for width of 5mm to 10mm and depth 80mm- 100mm including cost of cutting machine, generator & HOM of machinery, including cost of blade, coolant etc., including cleaning of groove & providing sand and hot bitumen fillers, and filler metal etc., including cost of conveyance of all materials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications.	mtr	108.00	Rupees One Hundred Eight Only
9	329.36	Loading and unloading of stone boulder/stone aggregates/sand/kanker/moorum. KSRRB M 100-1. Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications.	cum	108.64	Rupees One Hundred Eight and Sixty Four Paise Only

Signature of the Contractor

"D.T.S. APPROVED"

Executive Engineer
Rajarajeshwarinagara Division
B.B.M.P

21/12
2023